

RISK ASSESSMENT & CONTROL MEASURES

MOBILE SCAFFOLDS/SPANDECKS

Instant Scaffolds WA
 PO Box 129
 Burswood WA 6100
 Ph: 9472 7600 Fx: (08) 9472 7611

<u>Task Description</u>	<u>Hazard</u>	<u>Initial Class</u> 5	<u>Risk Class</u> 4	<u>Class</u> 3	<u>Control Measures</u>	<u>Class</u> 2	<u>Comments</u>	<u>Responsible Operator/Supervisor</u>
Erection	Unstable Ground			✓	Ensure correct size soleboards are placed under <u>all standards to distribute weight.</u>	✓	Relevant training <u>induction and qualifications (ticket)</u>	Supervisor
					Ensure scaffold is tagged "Unsafe" until erection is complete. Once complete a handover certificate (Tag) is to be completed.	✓	Relevant training	Supervisor
	Power Lines (electrocution)	✓			Ensure relevant authority has disconnected power or insulated power supply prior to erection.	✓	Relevant training	Supervisor
					Once scaffold is erected, install plywood to face of scaffold adjacent to power lines.	✓	Relevant training	
	Falling	✓			During erection, ensure that all scaffolds have handrails at 1.0m or safety harness and inertia reel/static line.	✓	Induction of safe procedures prior to erection.	All
	Overturing	✓			Ensure that scaffold is correctly tied into building every 4.0m in height.	✓	Induction of safe procedures prior to erection.	All
	Collapse	✓			Ensure that scaffold is built to manufacturers specifications - not to leave out any items such as braces, safety fittings, toeboards, S.W.L signs.	✓	Relevant training.	All
	Head, eye injury, cuts, burns etc.		✓		Wear hard hats and all relevant personal protection equipment.	✓	Relevant training and induction on manufacturers specifications.	All
Use of scaffold	Electrocution	✓			Do not remove any plywood, insulation, warning signs from area near	✓	Relevant safety inductions.	All
	Overturing	✓			Ensure that all ties are not modified, moved or removed unless done by ticketed scaffolders according to regulations.	✓	Relevant site safety induction.	All
	Collapse	✓			Adhere to SWL (Safe Working Load) of scaffold. Do not overload with materials or personnel	✓	Certificate of Competency required.	All
	Personal injury			✓	Ensure helmets and all personal protection equipment are worn at all times.	✓	Relevant induction once installed.	All
	Fall from scaffold	✓			Do not remove any component, handrails, midrails, braces, ladders, toeboards, platforms, frames, couplers or ties that could render the scaffold unsafe.	✓	Site specific induction	All
Dismantle of scaffold	Falling debris	✓			Ensure work platform is clean prior to dismantle of scaffold. Do not remove lower ties until scaffold is dismantled down to that level.	✓	Certificate of Competency required.	Supervisor/All
	Overturing	✓			Do not remove lower ties until scaffold is dismantle down to that level.	✓	Site specific induction	Supervisor
	Personal injury			✓	Wear all personal protective equipment and ensure that all knots are securely tied when lowering equipment.	✓	Certificate of Competency required. Site specific induction & training on ropes.	All

Level of risk & Description: ⑤CATASTROPHIC, ④MAJOR, ③MODERATE, ②MINOR, ①INSIGNIFICANT

See reserve side for special scaffold structures

Task Description	Hazard	Risk 5	Risk 4	Control Measures	Class 2	Comments	Responsible Operator/Supervisor
Erection/alteration or dismantle of scaffold	Accidental collapse	✓		Place bracing as indicated on erection procedures sketch provided.	✓	Refer to 1A erection guide provided	Operator
				Ensure castor/base plate leg fitted correctly and leg lock secured properly.		Safety details: refer to erection guide	Operator
				Ensure scaffold is on either level ground or correctly leveled using spirit level.		Safety details: refer to erection guide	Operator
				Ensure interlocking clips on frames are fitted and all bushings secured correctly inside Frame		Safety details: refer to erection guide	Operator
				Ensure scaffold has internal ladder access and hatch platform opens to outer perimeter of scaffold as instructed.		Refer to 1A erection guide provided	Operator
				Ensure platform fitted on transoms of scaffold correctly.		Refer to 1A erection guide provided	Operator
				Ensure kickboards fitted to scaffold perimeter correctly.		Refer to 1A erection guide provided	Operator
Whilst working on scaffold	Bodily harm ie. eye injury, head injury, cuts/abrasions, dust inhalation		✓	Ensure personnel protective equipment is being worn where required.	✓	Relative Training / Induction	Foreman
	Falling from scaffold	✓		Do not climb on scaffold handrail		Relevant Training	Operator/Supervisor
				Do not lean out of scaffold deck area		Refer to 1A erection guide - handrail installation	Foreman/Operator
				Ensure castors locked/chocked to prevent movement when in working position. Ensure leg locks/threaded leg adjusters are locked in place		Safety decals, refer to erection guide	Operator
				Do not move/mobile scaffold while person working on it		Refer to Erection site inspection	Foreman/Operator
				Do not use extension ladder/crates or any other material to increase reaching height on existing work level.		Call 1A to arrange a site inspection	All
				Do not climb up/down outside of scaffold to get to work level.		Refer 1A erection guide-ladder access	Foreman/Operator
				Do not remove guardrails/handrails		Refer to Safety needs & 1A supplier erection guides	All
	Overloading	✓		Ensure SWL of 225Kg not exceeded and that scaffold has one work level only.	✓	Refer to Safety needs & 1A supplier erection guides	All
	Electrocution	✓		Ensure scaffold is set to the correct safe clearance from power lines (consult local authority)	✓	Refer to Safety decals	Foreman/Operator
SPANDECKS							
	Accidental Collapse	✓		Ensure Spandek ends suspended over transoms of frames sitting flush with frame.	✓	Refer to Spandek erection guide and is unsure call 1A	Foreman/Operator
				Place guardrail posts at the end and middle of Spandek, coupler, tube, guardrails into position.		Refer to Spandek erection guide and is unsure call 1A	Operator
	Whilst working on Spandek	✓		Ensure guardrails positioned correctly and couplers tightened.	✓	Refer to Spandek erection guide and is unsure call 1A	Operator
	Falling from Spandek	✓		Do not climb on Spandek handrail.	✓	Refer to Spandek erection guide and is unsure call 1A	Handrail/Operator
				Do not lean out of Spandek work area.	✓	Refer to Spandek erection guide and is unsure call 1A	Foreman/Operator
	Overloading	✓		Ensure SWL of 225Kg is not exceeded.	✓	Safety needs - refer to Spandek erection guides	All
	Incorrectly installing Scaffold	✓		Ensure prior to erecting Spandecks that towers are built according to IA WorkCover specifications	✓	Refer 1A erection guide for information	Foreman/Operator
	Fall while installing	✓		Minimum 2 people to install	✓	Refer 1A erection guide for information	Foreman/Operator
	Tower Collapse during hoisting	✓		Ensure both towers are correctly secured tied before hoisting Spandecks.	✓	Refer 1A erection guide for information	Foreman/Operator
	Fall from tower whilst hoisting spans	✓		If safety harness is required, connect to approved point other than mobile scaffold unless approved by WorkCover.	✓	Refer 1A erection guide for information	Foreman/Operator
	Tower collapse after install	✓		If mobile arrangement, ensure bases of towers adequately tied to prevent spread under load.	✓	Use same size tube as handrails	Foreman/Operator
	Tower collapsing from rocking motion	✓		Ensure face bracing is applied correctly.	✓	Refer 1A erection guide for information	Foreman/Operator

Level of risk & Description:

⑤CATASTROPHIC, ④MAJOR, ③MODERATE, ②MINOR, ①INSIGNIFICANT

See reverse side for mobile scaffolds